BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT14633

APPROVED SCHEDULE - B

No EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Road Widdening and Improvements to Roads from Mariyannapalya to Coffe Board Layout in ward no 07 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRATAP	
				In Figures	In Words
1	330	Removing BS Slab of drain and stacking.	SQM	61.2	Rupees Sixty One and Twenty Paise Only
2	915	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	CUM	79.5	Rupees Seventy Nine and Fifty Paise Only
3	127.5	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.	SQM	19.25	Rupees Nineteen and Twenty Five Paise Only
4	1275	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.	SQM	4.7	Rupees Four and Seventy Paise Only
5	127.5	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	CUM	1510.0	Rupees One Thousand Five Hundred Ten Only
6	191.25	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	CUM	5315.0	Rupees Five Thousand Three Hundred Fifteen Only
7	200.25	KProviding and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum)	CUM	6136.55	Rupees Six Thousand One Hundred Thirty Six and Fifty Five Paise Only
8	476	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km	CUM	76.5	Rupees Seventy Six and Fifty Paise Only
9	41	Providing JCB Per DAY Pg no : xxxxvi i.no : 23 PWD SR 2014-15	Days	7053.0	Rupees Seven Thousand Fifty Three Only
10	55	Engaging Tracter 50HP Pg no : xxxxvii, i.no : 38 PWD SR 2014-15	Days	2350.0	Rupees Two Thousand Three Hundred Fifty Only

H.R.

H.V. Engg.
ಕ.ಅ.(ಬ್ಯಾ.ಎ) 3/3/16

11	500	Engaing of Labour Pg no L1V, i.no : 5 PWD SR 2014-15	Days	235.0	Rupees Two Hundred Thirty Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

3/3/16